ARCHITECTURAL DRAWINGS

ISSUE : 11/02/2026 | VERSION : 2.6

JSC Board & Batten Weatherboards

- Flexible Underlay 20mm Cavity Fix

GENERAL NOTES

OVERVIEW :

JSC Board & Batten is a cavity based external wall cladding system comprising of:

- Timber weatherboards finished with high quality exterior grade coatings
- H3.2 treated timber castellated cavity battens
- Proprietary mouldings
- Flashings and accessories

This documentation covers the fixing instructions for the installation of JSC Board & Batten weatherboards over JSC-U 20mm thick castellated cavity battens.

The information is this document has been specifically grouped in 2 different layouts to help Architects, Designers & Builders on site.

1. **A3/A1 ARCHITECTURAL DRAWINGS:**
   Similar details are grouped in A1/A3 format that make it easier to import into the project plan.
2. **A4 SITE DRAWINGS**
   Same information is made available on a A4 page at a larger scale for builders making it easier to read and distribute the drawings on site.

SCOPE OF USE

- This document is for use exclusively within the scope of JSC board & batten Weatherboard Cladding System technical documentation and Code Compliance CodeMark certificate CMNZ30083.
- Details are subject to change without notification and only the current version is compliant.
- Refer to www.jsc.co.nz at the time of use for the current documentation.
- The designer/specifier must be satisfied that these details are applicable for their intended use.

FIXING SPECIFICATION

SPECIES	FIXINGS MATERIAL
Western Red Cedar	316 Stainless Steel or Silicon Bronze annular grooved nails
Alaskan Yellow Cedar	316 Stainless Steel or Silicon Bronze annular grooved nails
Radiata Pine / Nordic Pine	316 Stainless Steel or Silicon Bronze annular grooved nails
JSC-TMT Thermally Modified Timber	
TMT TAIGA (RW/WW)	316 Stainless Steel or Silicon Bronze annular grooved nails
TMT TAXON	
TMT TUSCAN	
TMT AMBA	
TMT THERMOPINE	
TMT THERMOPINE H3.2	

A3/A1 ARCHITECTURAL DRAWINGS INDEX

Sheet Number	Sheet Title
JSC 20CF BB00	COVER SHEET - JSC BOARD & BATTEN CLADDING
JSC 20CF BB15	WINDOW DETAILS - Aluminium Joinery
	BB10 - Window Head Detail - Aluminium Joinery
	BB11 - Window Sill Detail - Aluminium Joinery
	BB12 - Window Jamb Detail - Aluminium Joinery
	BB13 - Window Flashing Details - Aluminium Joinery
JSC 20CF BB25	DOOR DETAILS - Head, Sill & Jamb - Aluminium Joinery
	BB20 - Door Head Detail - Aluminium Joinery
	BB21 - Door Sill Detail - Aluminium Joinery
	BB22 - Door Jamb Detail - Aluminium Joinery
	BB23 - Door Flashing Detail - Aluminium Joinery
JSC 20CF BB35	METER BOX DETAILS - Head, Sill & Jamb
	BB30 - Meter Box Head Detail
	BB31 - Meter Box Sill Detail
	BB32 - Meter Box Jamb Detail
	BB33 - Meter Box Flashing Detail
JSC 20CF BB46	GENERAL DETAILS 01 - Weatherboard Fixing
	BB40 - Weatherboard Fixing Detail
	BB41 - Weatherboard Scarf Joint
	BB42 - Base of Wall, Timber
	BB43 - Base of Wall, Timber
	BB44 - Pipe Penetration
	BB45 - 3D- Pipe Penetration
JSC 20CF BB66	GENERAL DETAILS 02 - Corners
	BB60 - Internal Corner
	BB61 - 3D - Internal Corner
	BB62 - External Corner
	BB63 - 3D - External Corner
JSC 20CF BB76	GENERAL DETAILS 04 - Parapet Saddle Flashing
	BB70 - Base of Wall, Membrane Roof
	BB71 - Deck of Roof Membrane - Parapet Saddle Flashing - STAGE ONE
	BB72 - Deck of Roof Membrane - Parapet Saddle Flashing - STAGE TWO
	BB73 - Deck of Roof Membrane - Parapet Saddle Flashing - STAGE THREE
	BB74 - Typical Parapet - Capping Joint Details
	BB75 - Parapet Section to Membrane Roof
JSC 20CF BB86	GENERAL DETAILS 05
	BB80 - Drained Inter Storey Joint
	BB81 - Apron Flashing Roof To Wall Junction
	BB82 - Soffit Detail at Wall
	BB83 - Soffit Detail at Fascia
	BB84 - Parapet Detail

JSC PREMIUM ARCHITECTURAL & BUILDING SOLUTIONS

EMAIL: TECHHELP@JSC.CO.NZ
WEBSITE: WWW.JSC.CO.NZ
Phone: 09 412 2812 (Technical)

CodeMark CMNZ30083

TYPE
BOARD & BATTEN WB - 20MM CAVITY FIX

NAME
COVER SHEET - JSC BOARD & BATTEN CLADDING

- TO BE READ IN CONJUNCTION WITH COMPLETE JSC BOARD & BATTEN SYSTEM LITERATURE
- DETAILS MAY BE SUBJECT CHANGE WITHOUT NOTICE

DRAWING SCALE	ISSUE DATE
NTS	11/02/2026
DRAWING NUMBER	**VERSION**
JSC 20CF BB00	2.6



W1 BB10 WINDOW HEAD - Board & Batten System
Cavity Fix - Aluminium Joinery - Double Glazing
SCALE 1:2 @ A1, 1:4 @ A3



NOTE : No Scriber Option :
The Aluminium Joinery must sit hard against the back of the joinery flange and the timber weatherboards with a E.P.S Compressible bond breaker foam seal between

W3 BB12 WINDOW JAMB - Board & Batten System
Cavity Fix - Aluminium Joinery - Double Glazing
SCALE 1:2 @ A1, 1:4 @ A3



W4 BB13 TYPICAL WINDOW OPENING (FLASHING TAPE)
SCALE : N.T.S



W5 BB13 FLEXIBLE BUILDING WRAP AT OPENING
SCALE : 1 / 5 @ A1, 1 / 10 @ A3



W2 BB11 WINDOW SILL - Board & Batten System
Cavity Fix - Aluminium Joinery - Double Glazing
SCALE 1:2 @ A1, 1:4 @ A3

LEGEND :

- AJ — ALUMINIUM JOINERY: Selected double glazed aluminium joinery. To E2/AS1 9.1.9
- BW — BUILDING WRAP: Flexible Wall Underlay, As per NZBC E2/AS1 - Table C.2.1.1, In extra high wind zones, Rigid Underlay required (9.1.6.2 E2/AS1)
- CB1 — CAVITY BATTEN - NON STRUCTURAL : Horizontally installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges.
- CB2 — CAVITY BATTEN - NON STRUCTURAL : Vertically installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges. Site machined to allow for flashing.
- CC — CAVITY CLOSURE: Cavity closure strip, positioned to give a 15mm min. drip edge to cladding
- FT1 — FLASHING TAPE: Flashing tape over wrap 70mm (50 min) turn-down required in corners only. Refer to Fig. 9.1.9.6 of NZBC E2/AS1
- FT2 — FLEXIBLE FLASHING TAPE: Flexible flashing tape lapped over aluminium head flashing or 2nd layer of Building Wrap, taped joint to top of timber frame
- HF — HEAD FLASHING: Aluminium head flashing with minimum 15 degree fall, optional hemmed edges as per table 4.5.1.1 E2/AS1
- IL — INTERNAL LINING: Selected Internal Lining
- IN — INSULATION: Selected Insulation
- PEF — PEF ROD BACKING: Foam backing rod with sealant to cavity in Window perimeter that forms a waterproof air-seal. (Sealant 2:1 Ratio)
- TF — TIMBER FRAME: H1.2 min treated timber framing
- TP — TIMBER PACKER: Tan H3.2 Treated Packer
- VBC — VERTICAL BOARD: Selected JSC Board Profile
- VBA — VERTICAL BATTEN: Selected JSC Batten Profile
- WL — WINDOW LINER: As Specified
- WH — WEATHERHEAD: (OPTIONAL) Selected JSC Horizontal batten above meter box as necessary to suit profile, shaped to shed water, sealant to back of head scriber
- WS — WINDOW SCRIBER: Sealant to back of scriber and 75 x 3.15mm 316 Stainless Steel nail in 3mm predrilled hole.
- WZ — WANZ SUPPORT: Provide window support as required by joinery manufacturer

GENERAL NOTES :

1. JSC Board & Batten System must be installed by a suitably qualified and experienced trade person. Where Restricted Building Work (RBW) applied the installer shall be a Licensed Building Practitioner (LBP) or supervised by LBP.
2. Weatherboards must be dry and free of any contamination.
3. Board lengths must be optimised prior the installation to avoid any unnecessary wastage and joints.
4. Any loose or bark encased knots or other timber defects need to be removed.
5. Weatherboards must be coated with exterior grade premium coating on all 4 sides in accordance with coating manufacturer specification.
6. Where weatherboards have an exposed bottom edge, the back of the boards should be cut with a 15° drip edge and cut end should be coated up to 75-150mm up from the bottom edge.
7. Cavity closer/vermin proofing must be installed continuously around the bottom of the cavity.
8. Cavity closer/vermin proofing openings must be kept clear and unobstructed to maintain draining and venting of the cavity.
9. For windows and doors, head flashing stop ends must be in place.
10. Flashings at corners, doors, windows and wall intersections must be installed to prevent water from entering the cavity.



ONE PIECE PC ALUMINIUM HEAD FLASHING 15° SLOPE WITH 10mm min COVER TO JOINERY EXTEND 30mm min EITHER SIDE OF JOINERY WITH STOP ENDS

W6 BB13 TYPICAL HEAD & FLASHING JOINT
SCALE : 1 / 2 @ A1, 1 / 4 @ A3

JSC PREMIUM ARCHITECTURAL & BUILDING SOLUTIONS

EMAIL: TECHHELP@JSC.CO.NZ
WEBSITE: WWW.JSC.CO.NZ
Phone: 09 412 2812 (Technical)

CodeMark CMNZ30083

TYPE
BOARD & BATTEN WB - 20MM CAVITY FIX

NAME
WINDOW DETAILS - Aluminium Joinery

- TO BE READ IN CONJUNCTION WITH COMPLETE JSC BOARD & BATTEN SYSTEM LITERATURE
- DETAILS MAY BE SUBJECT CHANGE WITHOUT NOTICE

DRAWING SCALE	ISSUE DATE
1:2 @ A1 1:4 @ A3	11/02/2026
DRAWING NUMBER	**VERSION**
JSC 20CF BB15	2.6



D1 BB20 — DOOR HEAD - Board & Batten System
Cavity Fix - Aluminium Joinery - Double Glazing
SCALE 1:2 @ A1, 1:4 @ A3



NOTE : No Scriber Option :
The Aluminium Joinery must sit hard against the back of the joinery flange and the timber weatherboards with a E.P.S Compressible bond breaker foam seal between

D3 BB22 — DOOR JAMB - Board & Batten System
Cavity Fix - Aluminium Joinery - Double Glazing
SCALE 1:2 @ A1, 1:4 @ A3



D4 BB23 — TYPICAL DOOR OPENING (FLASHING TAPE)
SCALE : N.T.S



D5 BB23 — FLEXIBLE BUILDING WRAP AT OPENING
SCALE : 1 / 5 @ A1, 1 / 10 @ A3

LEGEND :

- AJ — ALUMINIUM JOINERY: Selected double glazed aluminium joinery. To E2/AS1 9.1.9
- BW — BUILDING WRAP: Flexible Wall Underlay, As per NZBC E2/AS1 - Table C.2.1.1, In extra high wind zones, Rigid Underlay required (9.1.6.2 E2/AS1)
- CB1 — CAVITY BATTEN - NON STRUCTURAL : Horizontally installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges.
- CB2 — CAVITY BATTEN - NON STRUCTURAL : Vertically installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges. Site machined to allow for flashing.
- CC — CAVITY CLOSURE: Cavity closure strip, positioned to give a 15mm Min drip edge to cladding
- DL — DOOR LINER: As Specified
- DS — DOOR SCRIBER: Sealant to back of scriber and 75 x 3.15mm 316 Stainless Steel nail in 3mm predrilled hole.
- FT1 — FLASHING TAPE: Flashing tape over wrap 70mm (50 min) turn-down required in corners only. Refer to Fig. 9.1.9.6 of NZBC E2/AS1
- FT2 — FLEXIBLE FLASHING TAPE: Flexible flashing tape lapped over aluminium head flashing or 2nd layer of Building Wrap, taped joint to top of timber frame
- HF — HEAD FLASHING: Aluminium head flashing with minimum 15 degree fall, optional hemmed edges as per table 4.5.1.1 E2/AS1
- IL — INTERNAL LINING: Selected Internal Lining
- IN — INSULATION: Selected Insulation
- PEF — PEF ROD BACKING: Foam backing rod with sealant to cavity in Window perimeter that forms a waterproof air-seal. (Sealant 2:1 Ratio)
- TF — TIMBER FRAME: H1.2 min treated timber framing
- TP — TIMBER PACKER: Tan H3.2 Treated Packer
- VBC — VERTICAL BOARD: Selected JSC Board Profile
- VBA — VERTICAL BATTEN: Selected JSC Batten Profile
- WH — WEATHERHEAD: (OPTIONAL) Selected JSC Horizontal batten above meter box as necessary to suit profile, shaped to shed water, sealant to back of head scriber
- WZ — WANZ SUPPORT: Provide window support as required by joinery manufacturer



D2 BB21 — DOOR SILL - Board & Batten System
Cavity Fix - Aluminium Joinery - Double Glazing
SCALE 1:2 @ A1, 1:4 @ A3

GENERAL NOTES :

1. JSC Board & Batten System must be installed by a suitably qualified and experienced trade person. Where Restricted Building Work (RBW) applied the installer shall be a Licensed Building Practitioner (LBP) or supervised by LBP.
2. Weatherboards must be dry and free of any contamination.
3. Board lengths must be optimised prior the installation to avoid any unnecessary wastage and joints.
4. Any loose or bark encased knots or other timber defects need to be removed.
5. Weatherboards must be coated with exterior grade premium coating on all 4 sides in accordance with coating manufacturer specification.
6. Where weatherboards have an exposed bottom edge, the back of the boards should be cut with a 15° drip edge and cut end should be coated up to 75-150mm up from the bottom edge.
7. Cavity closer/vermin proofing must be installed continuously around the bottom of the cavity.
8. Cavity closer/vermin proofing openings must be kept clear and unobstructed to maintain draining and venting of the cavity.
9. For windows and doors, head flashing stop ends must be in place.
10. Flashings at corners, doors, windows and wall intersections must be installed to prevent water from entering the cavity.



ONE PIECE PC ALUMINIUM HEAD FLASHING 15° SLOPE WITH 10mm minimum COVER TO JOINERY EXTEND 30mm min EITHER SIDE OF JOINERY WITH STOP ENDS

D6 BB23 — TYPICAL HEAD & FLASHING JOINT
SCALE : 1 / 2 @ A1, 1 / 4 @ A3

JSC PREMIUM ARCHITECTURAL & BUILDING SOLUTIONS

EMAIL: TECHHELP@JSC.CO.NZ
WEBSITE: WWW.JSC.CO.NZ
Phone: 09 412 2812 (Technical)

CodeMark CMNZ30083

TYPE
BOARD & BATTEN WB - 20MM CAVITY FIX

NAME
DOOR DETAILS - Aluminium Joinery

- TO BE READ IN CONJUNCTION WITH COMPLETE JSC BOARD & BATTEN SYSTEM LITERATURE
- DETAILS MAY BE SUBJECT CHANGE WITHOUT NOTICE

DRAWING SCALE	ISSUE DATE
1:2 @ A1 1:4 @ A3	11/02/2026
DRAWING NUMBER	**VERSION**
JSC 20CF BB25	2.6



M1 BB30 METER BOX HEAD
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



M3 BB32 METER BOX JAMB
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



M4 BB33 TYPICAL METER BOX OPENING (FLASHING TAPE)
SCALE : N.T.S



M5 BB33 FLEXIBLE BUILDING WRAP AT OPENING
SCALE : 1 / 5 @ A1, 1 / 10 @ A3



M2 BB31 METER BOX SILL
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3

LEGEND:

- (BW) BUILDING WRAP: Flexible Wall Underlay, As per NZBC E2/AS1 - Table C.2.1.1, In extra high wind zones, Rigid Underlay required (9.1.6.2 E2/AS1)
- (CB1) CAVITY BATTEN - NON STRUCTURAL : Horizontally installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges.
- (CB2) CAVITY BATTEN - NON STRUCTURAL : Vertically installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges. Site machined to allow for flashing.
- (CC) CAVITY CLOSURE: Cavity closure strip, positioned to give a 15mm minimum drip edge to cladding
- (FT1) FLASHING TAPE: Flashing tape over wrap 70mm (50 min) turn-down required in corners only. Refer to Fig. 9.1.9.6 of NZBC E2/AS1
- (FT2) FLEXIBLE FLASHING TAPE: Flexible flashing tape lapped over aluminium head flashing or 2nd layer of Building Wrap, taped joint to top of timber frame
- (HF) HEAD FLASHING: Aluminium head flashing with minimum 15 degree fall, optional hemmed edges as per table 4.5.1.1 E2/AS1
- (IL) INTERNAL LINING: Selected Internal Lining
- (IN) INSULATION: Selected Insulation
- (PEF) PEF ROD BACKING: Foam backing rod with sealant to cavity in Window perimeter that forms a waterproof air-seal. (Sealant 2:1 Ratio)
- (MB) METER BOX: Electrical meter box, with removable hinged door and polycarbonate viewing window
- (MS) METER BOX SCRIBER: Sealant to back of scriber and 75 x 3.15mm 316 Stainless Steel nail in 3mm predrilled hole.
- (TF) TIMBER FRAME: H1.2 min treated timber framing
- (TP) TIMBER PACKER: Tan H3.2 Treated Packer
- (VBC) VERTICAL BOARD: Selected JSC Board Profile
- (VBA) VERTICAL BATTEN: Selected JSC Batten Profile
- (WL) WINDOW LINER: As Specified
- (WH) WEATHERHEAD: (OPTIONAL) Selected JSC Horizontal batten above meter box as necessary to suit profile, shaped to shed water, sealant to back of head scriber

GENERAL NOTES:

1. JSC Board & Batten System must be installed by a suitably qualified and experienced trade person. Where Restricted Building Work (RBW) applied the installer shall be a Licensed Building Practitioner (LBP) or supervised by LBP.
2. Weatherboards must be dry and free of any contamination.
3. Board lengths must be optimised prior the installation to avoid any unnecessary wastage and joints.
4. Any loose or bark encased knots or other timber defects need to be removed.
5. Weatherboards must be coated with exterior grade premium coating on all 4 sides in accordance with coating manufacturer specification.
6. Where weatherboards have an exposed bottom edge, the back of the boards should be cut with a 15° drip edge and cut end should be coated up to 75-150mm up from the bottom edge.
7. Cavity closer/vermin proofing must be installed continuously around the bottom of the cavity.
8. Cavity closer/vermin proofing openings must be kept clear and unobstructed to maintain draining and venting of the cavity.
9. For windows and doors, head flashing stop ends must be in place.
10. Flashings at corners, doors, windows and wall intersections must be installed to prevent water from entering the cavity.



ONE PIECE PC ALUMINIUM HEAD FLASHING 15° SLOPE WITH 10mm min COVER TO JOINERY EXTEND 30mm min EITHER SIDE OF JOINERY WITH STOP ENDS

M6 BB33 TYPICAL HEAD & FLASHING JOINT
SCALE : 1 / 2 @ A1, 1 / 4 @ A3

JSC PREMIUM ARCHITECTURAL & BUILDING SOLUTIONS

EMAIL: TECHHELP@JSC.CO.NZ
WEBSITE: WWW.JSC.CO.NZ
Phone: 09 412 2812 (Technical)

CodeMark CMNZ30083

TYPE
BOARD & BATTEN WB - 20MM CAVITY FIX

NAME
METER BOX DETAILS

- TO BE READ IN CONJUNCTION WITH COMPLETE JSC BOARD & BATTEN SYSTEM LITERATURE
- DETAILS MAY BE SUBJECT CHANGE WITHOUT NOTICE

DRAWING SCALE	ISSUE DATE
1:2 @ A1 1:4 @ A3	11/02/2026
DRAWING NUMBER	**VERSION**
JSC 20CF BB35	2.6



C1 BB40 — WEATHERBOARD FIXING
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C3 BB42 — BASE OF WALL, CONCRETE
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C4 BB43 — BASE OF WALL, TIMBER
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C5 BB44 — PIPE PENETRATION
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C2 BB41 — WEATHERBOARD SCARF JOINT
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3

LEGEND:

- BF — BACK FLASHING: Minimum 100mm Polypropylene or PVC rear flashing to provide 50mm cover past the scarf joint on each side
- BW — BUILDING WRAP: Flexible Wall Underlay, as per NZBC E2/AS1 - Table C.2.1.1. In extra high wind zones, Rigid Underlay required (9.1.6.2 E2/AS1)
- CB1 — CAVITY BATTEN - NON STRUCTURAL : Horizontally installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges.
- CC — CAVITY CLOSURE: Cavity closure strip, positioned to give a 15mm minimum drip edge to cladding
- FT4 — FLEXIBLE FLASHING TAPE: Flexible flashing tape lapped into corner, Refer NZBC E2/AS1 4.2.12 Flashing tape is recommended due to movement that may occur in corners. Not required by E2/AS1
- IL — INTERNAL LINING: Selected Internal Lining
- IN — INSULATION: Selected Insulation
- TF — TIMBER FRAME: H1.2 min treated timber framing
- VBO — VERTICAL BOARD: Selected JSC Board Profile
- VBA — VERTICAL BATTEN: Selected JSC Batten Profile

GENERAL NOTES:

1. JSC Board & Batten System must be installed by a suitably qualified and experienced trade person. Where Restricted Building Work (RBW) applied the installer shall be a Licensed Building Practitioner (LBP) or supervised by LBP.
2. Weatherboards must be dry and free of any contamination.
3. Board lengths must be optimised prior the installation to avoid any unnecessary wastage and joints.
4. Any loose or bark encased knots or other timber defects need to be removed.
5. Weatherboards must be coated with exterior grade premium coating on all 4 sides in accordance with coating manufacturer specification.
6. Where weatherboards have an exposed bottom edge, the back of the boards should be cut with a 15° drip edge and cut end should be coated up to 75-150mm up from the bottom edge.
7. Cavity closer/vermin proofing must be installed continuously around the bottom of the cavity.
8. Cavity closer/vermin proofing openings must be kept clear and unobstructed to maintain draining and venting of the cavity.
9. For windows and doors, head flashing stop ends must be in place.
10. Flashings at corners, doors, windows and wall intersections must be installed to prevent water from entering the cavity.



C6 BB45 — 3D PIPE PENETRATION
Cavity Fix - Board & Batten System
SCALE : N.T.S

PREMIUM ARCHITECTURAL & BUILDING SOLUTIONS
EMAIL: TECHHELP@JSC.CO.NZ
WEBSITE: WWW.JSC.CO.NZ
Phone: 09 412 2812 (Technical)

CodeMark CMNZ30083

TYPE
BOARD & BATTEN WB - 20MM CAVITY FIX

NAME
GENERAL DETAILS 01

- TO BE READ IN CONJUNCTION WITH COMPLETE JSC BOARD & BATTEN SYSTEM LITERATURE
- DETAILS MAY BE SUBJECT CHANGE WITHOUT NOTICE

DRAWING SCALE	ISSUE DATE
1:2 @ A1 1:4 @ A3	11/02/2026
DRAWING NUMBER	**VERSION**
JSC 20CF BB46	2.6



DETAIL NOTES :

1. Flashing tape is recommended due to movement that may occur in corners but it is not required by E2/AS1
2. Aluminium extrusion must not be continuous over solid floor joists.

C16 BB60 — INTERNAL CORNER DETAIL
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C17 BB61 — 3D INTERNAL CORNER - J44
Cavity Fix - Board & Batten System
SCALE : N.T.S



C18 BB62 — INTERNAL CORNER
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C19 BB63 — 3D INTERNAL CORNER
Cavity Fix - Board & Batten System
SCALE : N.T.S

LEGEND:

- BW — BUILDING WRAP: Flexible Wall Underlay, As per NZBC E2/AS1 - Table C.2.1.1, In extra high wind zones, Rigid Underlay required (9.1.6.2 E2/AS1)
- CB1 — CAVITY BATTEN - NON STRUCTURAL : Horizontally installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges.
- CB2 — CAVITY BATTEN - NON STRUCTURAL : Vertically installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges. Site machined to allow for flashing.
- CF — CORNER FLASHING: Aluminium, PVC or Stainless Steel corner flashing. Refer NZBC E2/AS1 Section 4.2.1.5 "Acceptable flashing materials" Minimum Flashing Size (mm) as per NZBC E2/AS1 Section 4.4.3:

FLASHING TYPE	L,M,H & VH Wind Zones	EH Wind Zones
Hemmed	50X50	75X75
Unhemmed	75x75	100x100

- FT3 — FLEXIBLE FLASHING TAPE: Flexible flashing tape lapped into corner, Refer NZBC E2/AS1 4.2.12 Flashing tape is recommended due to movement that may occur in corners. Not required by E2/AS1
- IL — INTERNAL LINING: Selected Internal Lining
- IN — INSULATION: Selected Insulation
- TF — TIMBER FRAME: H1.2 min treated timber framing
- VBC — VERTICAL BOARD: Selected JSC Board Profile
- VBA — VERTICAL BATTEN: Selected JSC Batten Profile

GENERAL NOTES:

PREMIUM ARCHITECTURAL & BUILDING SOLUTIONS
EMAIL: TECHHELP@JSC.CO.NZ
WEBSITE: WWW.JSC.CO.NZ
Phone: 09 412 2812 (Technical)

CodeMark CMNZ30083

TYPE: BOARD & BATTEN WB - 20MM CAVITY FIX
NAME: GENERAL DETAILS 02

- TO BE READ IN CONJUNCTION WITH COMPLETE JSC BOARD & BATTEN SYSTEM LITERATURE
- DETAILS MAY BE SUBJECT CHANGE WITHOUT NOTICE

DRAWING SCALE	ISSUE DATE
1:2 @ A1 1:4 @ A3	11/02/2026

DRAWING NUMBER	VERSION
JSC 20CF BB66	2.6



STAGE ONE



STAGE TWO



STAGE THREE





R2 BB71

DECK OR ROOF MEMBRANE PARAPET SADDLE FLASHING

Cavity Fix - Board & Batten System

SCALE 1:5 @ A1, 1:10 @ A3

R5 BB74

TYPICAL PARAPET CAPPING JOINT DETAILS

Cavity Fix - Board & Batten System

SCALE 1:5 @ A1, 1:10 @ A3



LEGEND:

- BW — BUILDING WRAP: Flexible Wall Underlay, As per NZBC E2/AS1 - Table C.2.1.1, In extra high wind zones, Rigid Underlay required (9.1.6.2 E2/AS1)
- CB1 — CAVITY BATTEN - NON STRUCTURAL : Horizontally installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges.
- CB2 — CAVITY BATTEN - NON STRUCTURAL : Vertically installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges. Site machined to allow for flashing.
- CC — CAVITY CLOSURE: Cavity closure strip, positioned to give a 15mm Min drip edge to cladding
- CF — CAP FLASHING: Continuous parapet flashing. Materials as per E2/AS1 4.2.1.5 + Figure 6.1.14A & Table 4.5.1.1
- FT — FLASHING TAPE: As per E2/AS1 4.2.12
- IL — INTERNAL LINING: Selected Internal Lining
- IN — INSULATION: Selected Insulation
- PSF — PARAPET SADDLE FLASHING: Materials as per E2/AS1 Part 4, refer E2/AS1 Figure 6.2.3.1A & 6.2.3.1B. Typically 0.45mm Min 316 Stainless Steel. Refer Table C.1.1.1A & Table C.1.1.1B for Comparability of Materials in Contact
- PB — PLYWOOD BACKING: 17mm CCA treated H3.2 grade plywood substrate
- RM — ROOFING MEMBRANE: Selected System on 17mm CCA treated H3.2 grade plywood glued and screwed to Rafters. Roof Membrane requires 400mm solid block support each way & solid support to all sheet edges
- TF — TIMBER FRAME: H1.2 min treated timber framing
- VBO — VERTICAL BOARD: Selected JSC Board Profile
- VBA — VERTICAL BATTEN: Selected JSC Batten Profile

GENERAL NOTES:

1. JSC Board & Batten System must be installed by a suitably qualified and experienced trade person. Where Restricted Building Work (RBW) applied the installer shall be a Licensed Building Practitioner (LBP) or supervised by LBP.
2. Weatherboards must be dry and free of any contamination.
3. Board lengths must be optimised prior the installation to avoid any unnecessary wastage and joints.
4. Any loose or bark encased knots or other timber defects need to be removed.
5. Weatherboards must be coated with exterior grade premium coating on all 4 sides in accordance with coating manufacturer specification.
6. Where weatherboards have an exposed bottom edge, the back of the boards should be cut with a 15° drip edge and cut end should be coated up to 75-150mm up from the bottom edge.
7. Cavity closer/vermin proofing must be installed continuously around the bottom of the cavity.
8. Cavity closer/vermin proofing openings must be kept clear and unobstructed to maintain draining and venting of the cavity.
9. For windows and doors, head flashing stop ends must be in place.
10. Flashings at corners, doors, windows and wall intersections must be installed to prevent water from entering the cavity.



R1 BB70

BASE OF WALL, MEMBRANE ROOF

Cavity Fix - Board & Batten System

SCALE 1:2.5 @ A1, 1:5 @ A3

R6 BB75

PARAPET SECTION TO MEMBRANE ROOF

Cavity Fix - Board & Batten System

SCALE 1:2.5 @ A1, 1:5 @ A3

JSC PREMIUM ARCHITECTURAL & BUILDING SOLUTIONS

EMAIL: TECHHELP@JSC.CO.NZ
WEBSITE: WWW.JSC.CO.NZ
Phone: 09 412 2812 (Technical)

CodeMark CMNZ30083

TYPE
BOARD & BATTEN WB - 20MM CAVITY FIX

NAME
GENERAL DETAILS 03

- TO BE READ IN CONJUNCTION WITH COMPLETE JSC BOARD & BATTEN SYSTEM LITERATURE
- DETAILS MAY BE SUBJECT CHANGE WITHOUT NOTICE

DRAWING SCALE	ISSUE DATE
1:2.5 @ A1 1:5 @ A3	11/02/2026
DRAWING NUMBER	**VERSION**
JSC 20CF BB76	2.6



C17 BB80 DRAINED INTER-STOREY JOINT
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C18 BB82 SOFFIT DETAIL AT WALL
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C19 BB83 SOFFIT DETAIL AT FASCIA
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C21 BB84 BALUSTARDE CAPPING OR PARAPET DETAIL
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3



C18 BB81 APRON FLASHING ROOF TO WALL JUNCTION
Cavity Fix - Board & Batten System
SCALE 1:2 @ A1, 1:4 @ A3

LEGEND:

- AF — APRON FLASHING: Materials as per E2/AS1 Part 4, Coating to match roofing material or refer E2/AS1 Table C.1.1.1B. Flashing Cover 130mm min. (L,M & H ≥ 10°) All others 200mm Refer Table 4.5.1.1 E2/AS1
- BW — BUILDING WRAP: Flexible Wall Underlay, As per NZBC E2/AS1 - Table C.2.1.1, In extra high wind zones, Ridgid Underlay required (9.1.6.2 E2/AS1)
- CB1 — CAVITY BATTEN - NON STRUCTURAL : Horizontally installed JSC-U 45mm x 20mm Radiata Pine H3.2 treated, both face castellated and 18° bevelled edges.
- CC — CAVITY CLOSURE: Cavity closure strip, positioned to give a 15mm Min drip edge to cladding
- IL — INTERNAL LINING: Selected Internal Lining
- IN — INSULATION: Selected Insulation
- HS — HEAD SOFFIT SCRIBER: JSC 27 mm x 40 mm Fix with 75 x 3.15mm 316 S.S nail in 2.5mm predrilled hole
- MR — METAL ROOFING : Selected Metal Roofing
- SL — SOFFIT LINING: JSC Soffit Lining
- TF — TIMBER FRAME: H1.2 min treated timber framing
- TP — TIMBER PACKER: Cant Strip, H3.2 Treated at 300crs to allow ventilation over the top of the wall.
- RU — ROOFING UNDERLAY: Selected Roofing Underlay As Per AS/AZS4200 with Mesh or Self Supported
- VBC — VERTICAL BOARD: Selected JSC Board Profile
- VBA — WEATHERBOARD: Selected JSC Board & Batten Weatherboard

GENERAL NOTES:

1. All Board & Batten Systems must be installed by a suitably qualified and experienced trade person. Where Restricted Building Work (RBW) applied the installer shall be a Licensed Building Practitioner (LBP) or supervised by LBP.
2. Weatherboards must be dry and free of any contamination.
3. Board lengths must be optimised prior the installation to avoid any unnecessary wastage and joints.
4. Any loose or bark encased knots or other timber defects need to be removed.
5. Weatherboards must be coated with exterior grade premium coating on all 4 sides in accordance with coating manufacturer specification.
6. Where weatherboards have an exposed bottom edge, the back of the boards should be cut with a 15° drip edge and cut end should be coated up to 75-150mm up from the bottom edge.
7. Cavity closer/vermin proofing must be installed continuously around the bottom of the cavity.
8. Cavity closer/vermin proofing openings must be kept clear and unobstructed to maintain draining and venting of the cavity.
9. For windows and doors, head flashing stop ends must be in place.
10. Flashings at corners, doors, windows and wall intersections must be installed to prevent water from entering the cavity.

JSC PREMIUM ARCHITECTURAL & BUILDING SOLUTIONS
EMAIL: TECHHELP@JSC.CO.NZ
WEBSITE: WWW.JSC.CO.NZ
Phone: 09 412 2812 (Technical)

CodeMark CMNZ30083

TYPE
BOARD & BATTEN WB - 20MM CAVITY FIX

NAME
GENERAL DETAILS 04

- TO BE READ IN CONJUNCTION WITH COMPLETE JSC BOARD & BATTEN SYSTEM LITERATURE
- DETAILS MAY BE SUBJECT CHANGE WITHOUT NOTICE

DRAWING SCALE	ISSUE DATE
1:2 @ A1 1:4 @ A3	11/02/2026
DRAWING NUMBER	VERSION
JSC 20CF BB86	2.6